




Panel M2 - Rack C2 Hardware Allocation & Field Terminal Schedule							
Slot	Module Catalog	Description / Module Function	I/O Type	Channels	Terminal Strip	Connected Junction Boxes / Signals	Status
PS	1756-PA72	ControlLogix 85-265V AC Power Supply (72W @ 60C)	POWER	120/230VAC	Internal Rack	Chassis Backplane Power	ACTIVE (RED)
01	1756-IB32	32-Point 24VDC Sink/Source Digital Input	DI	32	C2S01-X1,X2	JB-402 & JB-602 Flow & Limit Switches	ACTIVE
02	1756-IB32	32-Point 24VDC Sink/Source Digital Input	DI	32	C2S02-X1,X2	JB-602 & JB-607 Field Inputs	ACTIVE
03	1756-IB32	32-Point 24VDC Sink/Source Digital Input	DI	32	C2S03-X1,X2	JB-607 Spray Dryer 7th Flr DI	ACTIVE
04	1756-IB32	32-Point 24VDC Sink/Source Digital Input	DI	32	C2S04-X1,X2	JB-607 Spray Dryer 7th Flr DI	ACTIVE
05	1756-IB32	32-Point 24VDC Sink/Source Digital Input	DI	32	C2S05-X1,X2	JB-607 Spray Dryer 7th Flr DI	ACTIVE
06	1756-OB32	32-Point 24VDC Source Digital Output	DO	32	C2S06-X1,X2	JB-402 & JB-602 On/Off Valves	ACTIVE
07	1756-OB32	32-Point 24VDC Source Digital Output	DO	32	C2S07-X1,X2	JB-607 Solenoid Valves (DO)	ACTIVE
08	1756-OB32	32-Point 24VDC Source Digital Output	DO	32	C2S08-X1,X2	JB-607 Solenoid Valves (DO)	ACTIVE
09	1756-IF16	16-Point High Resolution Analog Input	AI	16	C2S09-X1	JB-402 Jet Cooker Flow/Press AI	ACTIVE
10	1756-IF16	16-Point High Resolution Analog Input	AI	16	C2S10-X1	JB-602 Spray Dryer 3rd Flr AI	ACTIVE
11	1756-IF16	16-Point High Resolution Analog Input	AI	16	C2S11-X1	JB-602 Spray Dryer 3rd Flr AI	ACTIVE
12	1756-IF16	16-Point High Resolution Analog Input	AI	16	C2S12-X1	JB-607 Spray Dryer 7th Flr AI	ACTIVE
13	1756-IF16	16-Point High Resolution Analog Input	AI	16	C2S13-X1	JB-607 Spray Dryer 7th Flr AI	ACTIVE

PANEL M2 INSTALLATION SPECIFICATIONS & FIELD CONNECTIONS	
- ENCLOSURE SIZE: 800 mm (W) x 2000 mm (H) x 800 mm (D) + 100 mm plinth base. Single door.	- FIELD DESTINATIONS: Connects to field junction boxes: JB-602, JB-402, JB-607.
	- POWER INFEED: Dual redundant 24VDC feeder lines from Panel M1 distribution bus.
	- NETWORK ARCHITECTURE: Dual-ring EtherNet/IP Device Level Ring (DLR) connection.
	- CABLING RULES: All analog inputs wired with individually shielded twisted pairs (LiY-CY TP).
	- SHIELD GROUNDING: Cable screens grounded at panel entry copper earth bar only (single-point earthing).

INGREDION (THAILAND) CO., LTD. KALASIN STARCH PLANT - JET COOKER PROJECT		AEC INDUSTRIAL ENGINEERING SYSTEMS INTEGRATION & AUTOMATION	
PANEL M2 - SUBPANEL MOUNTING PLAN & COMPONENT SCHEDULE MAIN CONTROL CABINET CA1 / MOTOR CONTROL PANELS M1..M4		DOC NO: CA1-DWG-PL-004 REV: 3.6 DATE: 2026-09-07	
SCALE: 1:8	DRAWN: AEC-ENG	STATUS: APPROVED	SHEET: 4 / 7
PROJECT: JET COOKER	CHECKED: LEAD-PE		